APPROVED SHEATHING BOARD
ATTACHED PER APPLICABLE CODE

FRAMING MEMBER

APPROVED BUILDING WRAP
LAPPED OVER SCREED FLANGE

3/4" CEMENT PLASTER WITH
12 MIL (min) DFT DRYLOK EXTREME COATING

STRUCTALATH TWIN TRAC 2.5

FOUNDATION WEEP SCREED – USED FOR
SCREEDING AND PLASTER STOP

NOSE OF SCREED 1" BELOW CEMENT / WALL JUNCTION

FOUNDATION – PARGE COAT IF NEEDED

6" CLEARANCE FROM NOSE OF SCREED TO GRADE

GRADE SLOPE PER APPLICABLE CODE

1/8" CLEARANCE

1"

Stem Wall or Monolithic Foundation

SCS 02_1 FOUNDATION SCREED TERMINATION

Sealed Cladding System

SCS 02_01   07/01/2020

Note:
Details to be used in conjunction
with all applicable provisions
contained in the Sealed Cladding
System Design Manual.